One Stop Building & Remodeling

Detailed estimate

Validation — interior painting

Contact (optional): AI VALIDATION contact

Job address: Pending / none

314AE28B | 10/11/2026 | Revision 6 | Review plan 4

Prices need review

Assumptions: Unspecified heights assumed 8 ft after review. Fixed financial fixture, not supplier pricing.

Bedroom 1 — Painting

Included: Walls and baseboards

Excluded: Ceiling

Measurements / units: 9 × 12 ft, height 8 ft

Preparation: Protect and patch

Product / material: Duration Home walls; Duration Semi-Gloss baseboards

Finish / alternatives: Satin or eggshell: selection pending

Walls

4 GAL | Client unit price: $88.40 | Total: $353.60

Baseboards

1 GAL | Client unit price: $95.20 | Total: $95.20

Preparation

1 LOT | Client unit price: $34.00 | Total: $34.00

Labor

2.5 HR | Client unit price: $102.00 | Total: $255.00

Total: $737.80

Bedroom 2 — Painting

Included: Walls and baseboards

Excluded: Ceiling

Measurements / units: 9 × 13 ft, height 8 ft assumed

Preparation: Protect and patch

Product / material: Duration Home walls; Duration Semi-Gloss baseboards

Finish / alternatives: Satin or eggshell: selection pending

Assumptions: Height assumed 8 ft

Walls

3 GAL | Client unit price: $88.40 | Total: $265.20

Baseboards

1 GAL | Client unit price: $95.20 | Total: $95.20

Bedroom 2 (continued)

Preparation

1 LOT | Client unit price: $34.00 | Total: $34.00

Labor

2.5 HR | Client unit price: $102.00 | Total: $255.00

Total: $649.40

Bedroom 3 — Painting

Included: Walls and baseboards

Excluded: Ceiling

Measurements / units: 12 × 13 ft, height 8 ft assumed

Preparation: Protect and patch

Product / material: Duration Home walls; Duration Semi-Gloss baseboards

Finish / alternatives: Satin or eggshell: selection pending

Assumptions: Height assumed 8 ft

Walls

2 GAL | Client unit price: $88.40 | Total: $176.80

Baseboards

1 GAL | Client unit price: $95.20 | Total: $95.20

Preparation

1 LOT | Client unit price: $34.00 | Total: $34.00

Labor

3 HR | Client unit price: $102.00 | Total: $306.00

Total: $612.00

Bathroom — Painting

Included: Walls and baseboards

Excluded: Ceiling

Measurements / units: 6 × 7 ft, height 8 ft assumed

Preparation: Spot-prime only; protect and patch

Product / material: Duration Home walls; Duration Semi-Gloss baseboards

Finish / alternatives: Satin or eggshell: selection pending

Assumptions: Height assumed 8 ft

Walls

1 GAL | Client unit price: $88.40 | Total: $88.40

Spot primer

1 GAL | Client unit price: $47.60 | Total: $47.60

Baseboards

1 QT | Client unit price: $47.60 | Total: $47.60

Bathroom (continued)

Preparation

1 LOT | Client unit price: $27.20 | Total: $27.20

Labor

2 HR | Client unit price: $102.00 | Total: $204.00

Total: $414.80

Hallway — Painting

Included: Walls and baseboards

Excluded: Ceiling

Measurements / units: 16 × 3 ft, height 8 ft assumed

Preparation: Protect and patch

Product / material: Duration Home walls; Duration Semi-Gloss baseboards

Finish / alternatives: Satin or eggshell: selection pending

Assumptions: Height assumed 8 ft

Walls

2 GAL | Client unit price: $88.40 | Total: $176.80

Baseboards

1 QT | Client unit price: $47.60 | Total: $47.60

Preparation

1 LOT | Client unit price: $27.20 | Total: $27.20

Labor

2.5 HR | Client unit price: $102.00 | Total: $255.00

Total: $506.60

Living Room — Painting

Included: Walls, ceiling and baseboards

Excluded: No other surfaces

Measurements / units: 18 × 19 ft, height 8 ft assumed

Preparation: Protect and patch

Product / material: Duration Home walls; Interior Latex Flat Ceiling Paint ceiling

Finish / alternatives: Satin or eggshell: selection pending

Assumptions: Height assumed 8 ft

Walls

3 GAL | Client unit price: $88.40 | Total: $265.20

Interior Latex Flat Ceiling Paint

2 GAL | Client unit price: $61.20 | Total: $122.40

Baseboards

1 GAL | Client unit price: $95.20 | Total: $95.20

Living Room (continued)

Preparation

1 LOT | Client unit price: $47.60 | Total: $47.60

Labor

6 HR | Client unit price: $102.00 | Total: $612.00

Total: $1,142.40

Kitchen — Painting

Included: Walls only

Excluded: Ceiling and baseboards

Measurements / units: 24 LF × 5 ft high

Preparation: Protect and patch

Product / material: Duration Home walls

Finish / alternatives: Satin or eggshell: selection pending

Walls

1 GAL | Client unit price: $88.40 | Total: $88.40

Preparation

1 LOT | Client unit price: $20.40 | Total: $20.40

Labor

1 HR | Client unit price: $102.00 | Total: $102.00

Total: $210.80

Total: $4,273.80