One Stop Building & Remodeling

Detailed estimate

Bedroom wall painting

#11AEE45B | Date: 10/28/2026 | Revision 1 | Draft

Status: Draft

Client: Not provided
Project: Not provided

Web prices are budgeting references. No supplier account or contact, selected store or job ZIP is required. Purchase prices, tax and delivery may vary. Selecting a store does not refresh the observed date. Saved internal references; no live lookup. Tax, freight and stock unknown unless explicitly documented. Buying store and job ZIP are separate.

Provisional prices require review. Finalization does not approve prices.

Scope of work

Bedroom - Interior wall painting

Included: Walls, protection, preparation, minor nail-hole patching and cleanup

Excluded: Ceiling, trim, doors and large repairs

Measurements / units: Original measurements/request: Paint walls 12 x10 x8 ft; paint SKU 433052; current editable calculation: 12 x 10 x 8 ft; 352 sf

Preparation: Protect, prepare and patch minor nail holes once

Product / material: Approved plan reference; current selections in line items: Accepted budgeting alternative for SKU 433052; equivalence not confirmed. Synthetic supplier | SYNTHETIC Own finish paint 65 | 1 US gal | SKU OWN-65 | gal; The Home Depot | DAP DryDex Dry Time Indicator Spackling Paste | 32 oz as labeled | SKU 283433 | ea

Finish / alternatives: Approved plan reference; current selections in line items: Eggshell, Ultra Pure White

Assumptions: Original plan assumptions; current costs and overrides are in the line items. Two coats; 350 sf/gal; 10% waste; provisional productivity and consumables

Description	Quantity	Unit	Unit price	Amount
Bedroom				
Protect floor and furnishings Consumables allowance only; excludes separately counted paint and patch material. Editable provisional assumption - no confirmed local price	352	sf	$0.10665	$37.54
Protect floor and furnishings - labor 352 sf ÷ 800 per hour; rounded up to 0.01 hr. Editable provisional assumption - no confirmed local price	0.44	hr	$100.00	$44.00

Description	Quantity	Unit	Unit price	Amount
Prepare wall surfaces Consumables allowance only; excludes separately counted paint and patch material. Editable provisional assumption - no confirmed local price	352	sf	$0.08	$28.16
Prepare wall surfaces - labor 352 sf ÷ 350 per hour; rounded up to 0.01 hr. Editable provisional assumption - no confirmed local price	1.01	hr	$100.00	$101.00
DAP DryDex Dry Time Indicator Spackling Paste · 32 oz as labeled 1 whole repair package(s): editable purchase allowance, not yield per hole. Preparation excludes this material. SKU 283433 | model 12327 | ea | https://www.homedepot.com/p/DAP-DryDex-32-oz-Dry-Time-Indicator-Spackling-Paste-12327/100155689 | The Home Depot · DryDex Dry Time Indicator Spackling Paste · 32 oz as labeled · public online price; branch/ZIP unverified · 2026-10-17	1	ea	$15.30	$15.30
Minor wall patch material - labor 1 patches ÷ 8 per hour; rounded up to 0.01 hr. Editable provisional assumption - no confirmed local price	0.13	hr	$100.00	$13.00
SYNTHETIC Own finish paint 65 · 1 US gal Whole purchasable packages; coverage and waste are editable assumptions. 352 sf × 2 coats × (1 + 10% waste) ÷ 350 sf/gal = 2.2126 gal; 3 × 1 gal package(s). Coverage and waste are editable assumptions. Accepted budgeting alternative for SKU 433052; equivalence not confirmed. SKU OWN-65 | gal | https://example.invalid/qa-source | Synthetic supplier · Own finish paint 65 · 1 US gal · provisional price; review · 2026-10-25	3	gal	$27.533	$82.60
Interior wall paint - labor 704 coat-sf ÷ 150 per hour; rounded up to 0.01 hr. Editable provisional assumption - no confirmed local price	4.7	hr	$99.998	$469.99
Clean and remove protection Consumables allowance only; excludes separately counted paint and patch material. Editable provisional assumption - no confirmed local price	352	sf	$0.04	$14.08
Clean and remove protection - labor 352 sf ÷ 1000 per hour; rounded up to 0.01 hr. Editable provisional assumption - no confirmed local price	0.36	hr	$100.00	$36.00

Description	Quantity	Unit	Unit price	Amount
Job expenses allowance 5% of this room's material and labor cost; recalculated after edits. Excludes this line, equipment and other expenses. Tax and freight unconfirmed. Editable provisional assumption - no confirmed local price	1	lot	$42.08	$42.08

Subtotal	$883.75

TOTAL PROPOSAL

$883.75

Assumptions

Original plan assumptions; current costs and overrides are in the line items. Gross walls, no openings deducted. Template coverage, productivity, expenses and margin are editable assumptions; catalog prices are public online observations, not local quotes.

Prepared by One Stop

Authorized signature image not configured.

Client acceptance

Client name: _____

Client signature: _____

Acceptance date: _____

Blank signature lines do not record acceptance.

Finalization records this saved revision. It is not customer acceptance or internal price approval.