One Stop Building & Remodeling

Client proposal

Validation - interior painting

#4C9EEBF6 | Date: 10/17/2026 | Revision 4 | Draft

Status: Draft

Client: Not provided
Project: Not provided

Provisional prices require review. Finalization does not approve prices.

Scope of work

Bedroom 1 - Painting

Included: Walls and baseboards

Excluded: Ceiling

Measurements / units: 9 × 12 ft, height 8 ft

Preparation: Protect and patch

Product / material: Duration Home walls; Duration Semi-Gloss baseboards

Finish / alternatives: Satin or eggshell: selection pending

Bedroom 2 - Painting

Included: Walls and baseboards

Excluded: Ceiling

Measurements / units: 9 × 13 ft, height 8 ft assumed

Preparation: Protect and patch

Product / material: Duration Home walls; Duration Semi-Gloss baseboards

Finish / alternatives: Satin or eggshell: selection pending

Assumptions: Height assumed 8 ft

Bedroom 3 - Painting

Included: Walls and baseboards

Excluded: Ceiling

Measurements / units: 12 × 13 ft, height 8 ft assumed

Preparation: Protect and patch

Product / material: Duration Home walls; Duration Semi-Gloss baseboards

Finish / alternatives: Satin or eggshell: selection pending

Assumptions: Height assumed 8 ft

Bathroom - Painting

Included: Walls and baseboards

Excluded: Ceiling

Measurements / units: 6 × 7 ft, height 8 ft assumed

Preparation: Spot-prime only; protect and patch

Product / material: Duration Home walls; Duration Semi-Gloss baseboards

Finish / alternatives: Satin or eggshell: selection pending

Assumptions: Height assumed 8 ft

Hallway - Painting

Included: Walls and baseboards

Excluded: Ceiling

Measurements / units: 16 × 3 ft, height 8 ft assumed

Preparation: Protect and patch

Product / material: Duration Home walls; Duration Semi-Gloss baseboards

Finish / alternatives: Satin or eggshell: selection pending

Assumptions: Height assumed 8 ft

Living Room - Painting

Included: Walls, ceiling and baseboards

Excluded: No other surfaces

Measurements / units: 18 × 19 ft, height 8 ft assumed

Preparation: Protect and patch

Product / material: Duration Home walls; Interior Latex Flat Ceiling Paint ceiling

Finish / alternatives: Satin or eggshell: selection pending

Assumptions: Height assumed 8 ft

Kitchen - Painting

Included: Walls only

Excluded: Ceiling and baseboards

Measurements / units: 24 LF × 5 ft high

Preparation: Protect and patch

Product / material: Duration Home walls

Finish / alternatives: Satin or eggshell: selection pending

Description	Quantity	Unit	Unit price	Amount
Bedroom 1				
BEHR ULTRA Ultra Pure White Eggshell Interior Paint & Primer · 1 US gal · eggshell · Ultra Pure White Fixed arithmetic fixture; no productivity claim 352 sf × 2 coats × (1 + 0% waste) ÷ 350 sf/gal = 2.0115 gal; 3 × 1 gal package(s). Coverage and waste are editable assumptions. The Home Depot · BEHR ULTRA Ultra Pure White Eggshell Interior Paint & Primer · 1 US gal · eggshell · Ultra Pure White · public online price; branch/ZIP unverified · 2026-10-17	3	gal	$63.89	$191.68
Baseboards Fixed arithmetic fixture; no productivity claim Provisional assumption - no verified local price	1	gal	$95.20	$95.20
Preparation Fixed arithmetic fixture; no productivity claim Provisional assumption - no verified local price	1	lot	$34.00	$34.00
Labor Fixed arithmetic fixture; no productivity claim Provisional assumption - no verified local price	2.5	hr	$102.00	$255.00

Description	Quantity	Unit	Unit price	Amount
DAP DryDex Dry Time Indicator Spackling Paste · 32 oz as labeled The Home Depot · DryDex Dry Time Indicator Spackling Paste · 32 oz as labeled · public online price; branch/ZIP unverified · 2026-10-17	1	ea	$15.61	$15.61
Bedroom 2				
Walls Fixed arithmetic fixture; no productivity claim Provisional assumption - no verified local price	2	gal	$88.40	$176.80
Baseboards Fixed arithmetic fixture; no productivity claim Provisional assumption - no verified local price	1	gal	$95.20	$95.20
Preparation Fixed arithmetic fixture; no productivity claim Provisional assumption - no verified local price	1	lot	$34.00	$34.00
Labor Fixed arithmetic fixture; no productivity claim Provisional assumption - no verified local price	2.5	hr	$102.00	$255.00
Bedroom 3				
Walls Fixed arithmetic fixture; no productivity claim Provisional assumption - no verified local price	2	gal	$88.40	$176.80
Baseboards Fixed arithmetic fixture; no productivity claim Provisional assumption - no verified local price	1	gal	$95.20	$95.20
Preparation Fixed arithmetic fixture; no productivity claim Provisional assumption - no verified local price	1	lot	$34.00	$34.00
Labor Fixed arithmetic fixture; no productivity claim Provisional assumption - no verified local price	3	hr	$102.00	$306.00
Bathroom				
Walls Fixed arithmetic fixture; no productivity claim Provisional assumption - no verified local price	1	gal	$88.40	$88.40

Description	Quantity	Unit	Unit price	Amount
Spot primer Fixed arithmetic fixture; no productivity claim Provisional assumption - no verified local price	1	gal	$47.60	$47.60
Baseboards Fixed arithmetic fixture; no productivity claim Provisional assumption - no verified local price	1	qt	$47.60	$47.60
Preparation Fixed arithmetic fixture; no productivity claim Provisional assumption - no verified local price	1	lot	$27.20	$27.20
Labor Fixed arithmetic fixture; no productivity claim Provisional assumption - no verified local price	2	hr	$102.00	$204.00
Hallway				
Walls Fixed arithmetic fixture; no productivity claim Provisional assumption - no verified local price	2	gal	$88.40	$176.80
Baseboards Fixed arithmetic fixture; no productivity claim Provisional assumption - no verified local price	1	qt	$47.60	$47.60
Preparation Fixed arithmetic fixture; no productivity claim Provisional assumption - no verified local price	1	lot	$27.20	$27.20
Labor Fixed arithmetic fixture; no productivity claim Provisional assumption - no verified local price	2.5	hr	$102.00	$255.00
Living Room				
Walls Fixed arithmetic fixture; no productivity claim Provisional assumption - no verified local price	3	gal	$88.40	$265.20
Interior Latex Flat Ceiling Paint Fixed arithmetic fixture; no productivity claim Provisional assumption - no verified local price	2	gal	$61.20	$122.40
Baseboards Fixed arithmetic fixture; no productivity claim Provisional assumption - no verified local price	1	gal	$95.20	$95.20

Description	Quantity	Unit	Unit price	Amount
Preparation Fixed arithmetic fixture; no productivity claim Provisional assumption - no verified local price	1	lot	$47.60	$47.60
Labor Fixed arithmetic fixture; no productivity claim Provisional assumption - no verified local price	6	hr	$102.00	$612.00
Kitchen				
Walls Fixed arithmetic fixture; no productivity claim Provisional assumption - no verified local price	1	gal	$88.40	$88.40
Preparation Fixed arithmetic fixture; no productivity claim Provisional assumption - no verified local price	1	lot	$20.40	$20.40
Labor Fixed arithmetic fixture; no productivity claim Provisional assumption - no verified local price	1	hr	$102.00	$102.00
		Subtotal		$4,039.09

TOTAL PROPOSAL

$4,039.09

Assumptions

Unspecified heights assumed 8 ft after review. Fixed financial fixture, not supplier pricing.

Prepared by One Stop

Authorized signature image not configured.

Client acceptance

Client name: _____

Client signature: _____

Acceptance date: _____

Blank signature lines do not record acceptance.

Finalization records this saved revision. It is not customer acceptance or internal price approval.