One Stop Building & Remodeling

Detailed estimate

PRELIMINARY BUDGET

Preliminary budget: items with pending quantities or prices are not included in the known subtotal. You can save, finalize this document revision and export it; the full price remains to be defined.

Bedroom wall painting

#1764AE96 | Date: 10/28/2026 | Revision 8 | Draft

Status: Draft

Client: Not provided
Project: Not provided

Web prices are budgeting references. No supplier account or contact, selected store or job ZIP is required. Purchase prices, tax and delivery may vary. Selecting a store does not refresh the observed date. Saved internal references; no live lookup. Tax, freight and stock unknown unless explicitly documented. Buying store and job ZIP are separate.

Provisional prices require review. Finalization does not approve prices.

Scope of work

Bedroom - Interior wall painting

Included: Walls, protection, preparation, minor nail-hole patching and cleanup

Excluded: Ceiling, trim, doors and large repairs

Measurements / units: Original measurements/request: Paint walls 12 x10 x8 ft; paint SKU 433052; primer model 20941; current editable calculation: 30 x 10 x 8 ft; 640 sf

Preparation: Protect, prepare and patch minor nail holes once

Product / material: Approved plan reference; current selections in line items: The Home Depot | BEHR BEHR ULTRA Ultra Pure White Eggshell Interior Paint & Primer | 1 US gal · eggshell · Ultra Pure White | SKU 433052 | gal; The Home Depot | DAP DryDex Dry Time Indicator Spackling Paste | 32 oz as labeled | SKU 283433 | ea; The Home Depot | KILZ KILZ 2 ALL PURPOSE White Interior/Exterior Primer | 1 US gal · White | SKU - | gal

Finish / alternatives: Approved plan reference; current selections in line items: Eggshell, Ultra Pure White

Assumptions: Original plan assumptions; current costs and overrides are in the line items. Two coats; 350 sf/gal; 10% waste; provisional productivity and consumables

Description	Quantity	Unit	Unit price	Amount
Bedroom				

Description	Quantity	Unit	Unit price	Amount
Protect floor and furnishings Consumables allowance only; excludes separately counted paint and patch material. Editable provisional assumption - no confirmed local price	640	sf	$0.10666	$68.26
Protect floor and furnishings - labor 640 sf ÷ 800 per hour; rounded up to 0.01 hr. Editable provisional assumption - no confirmed local price	0.8	hr	$100.00	$80.00
Prepare wall surfaces Consumables allowance only; excludes separately counted paint and patch material. Editable provisional assumption - no confirmed local price	640	sf	$0.08	$51.20
Prepare wall surfaces - labor 640 sf ÷ 350 per hour; rounded up to 0.01 hr. Editable provisional assumption - no confirmed local price	1.83	hr	$99.995	$182.99
DAP DryDex Dry Time Indicator Spackling Paste · 32 oz as labeled 1 whole repair package(s): editable purchase allowance, not yield per hole. Preparation excludes this material. SKU 283433 | model 12327 | ea | https://www.homedepot.com/p/DAP-DryDex-32-oz-Dry-Time-Indicator-Spackling-Paste-12327/100155689 | The Home Depot · DryDex Dry Time Indicator Spackling Paste · 32 oz as labeled · public online price; branch/ZIP unverified · 2026-10-17	1	ea	$15.31	$15.31
Minor wall patch material - labor 1 patches ÷ 8 per hour; rounded up to 0.01 hr. Editable provisional assumption - no confirmed local price	0.13	hr	$100.00	$13.00
BEHR ULTRA Ultra Pure White Eggshell Interior Paint & Primer · 1 US gal · eggshell · Ultra Pure White Whole purchasable packages; coverage and waste are editable assumptions. 640 sf × 2 coats × (1 + 10% waste) ÷ 250 sf/gal = 5.632 gal; 6 × 1 gal package(s). Coverage and waste are editable assumptions. Sheet matched to model 275001; Ultra Pure White / eggshell; 1 US gal · eggshell · Ultra Pure White. Selected coverage 250 sf/gal per coat; documented range 250-400. Lower bound chosen for estimating; not a guarantee. Sheet 11/2020; consulted 2026-10-28; https://images.thdstatic.com/catalog/pdfImages/da/dae4efe2-cd05-4c12-b7f8-344757743ad9.pdf. Prepared, clean, dry substrate; texture, porosity and application affect coverage. Spray loss excluded. Coat count and job waste require review. No labor productivity inferred. Manual entry - provisional	6	gal	$65.332	$391.99

Description	Quantity	Unit	Unit price	Amount
Interior wall paint - labor 1280 coat-sf ÷ 150 per hour; rounded up to 0.01 hr. Editable provisional assumption - no confirmed local price	8.54	hr	$99.998	$853.98
Clean and remove protection Consumables allowance only; excludes separately counted paint and patch material. Editable provisional assumption - no confirmed local price	640	sf	$0.04	$25.60
Clean and remove protection - labor 640 sf ÷ 1000 per hour; rounded up to 0.01 hr. Editable provisional assumption - no confirmed local price	0.64	hr	$100.00	$64.00
KILZ 2 ALL PURPOSE White Interior/Exterior Primer · 1 US gal · White Primer: whole packages calculated from explicitly selected sheet and editable job inputs. No consumable labor added; primer application hours are reviewed separately. 640 sf × 1 coats × (1 + 10% waste) ÷ 300 sf/gal = 2.3467 gal; 3 × 1 gal package(s). Coverage and waste are editable assumptions. Current wall area explicitly selected. Sheet matched to model 20941; White / primer; sheen depends on substrate; 1 US gal · White. Selected coverage 300 sf/gal per coat; documented range 300-400. Lower bound chosen for estimating; not a guarantee. Sheet 03/2019 (legacy header 6/2014); consulted 2026-10-28; https://images.thdstatic.com/catalog/pdfImages/b5/b505644b-bcec-4656-9ad9-64839581d23d.pdf. Prepared, clean, dry substrate; texture, porosity and application affect coverage. Spray loss excluded. Coat count and job waste require review. No labor productivity inferred. model 20941 | gal | https://www.homedepot.com/p/KILZ-KILZ-2-ALL-PURPOSE-1-gal-White-Interior-Exterior-Multi-Surface-Primer-Sealer-and-Stain-Blocker-20941/100096395 | The Home Depot · KILZ 2 ALL PURPOSE White Interior/Exterior Primer · 1 US gal · White · public online price; branch/ZIP unverified · 2026-10-17	3	gal	$30.64	$91.92
Primer application - labor Primer application labor hours pending. Finish-paint coats/productivity do not establish primer labor. Confirm incremental hours, or explicitly enter zero if already included; no extra hours assumed. Editable provisional assumption - no confirmed local price	-	hr	$100.00	Price pending
Job expenses allowance 5% of this room’s material and labor cost; recalculated after edits. Excludes this line, equipment and other expenses. Tax and freight unconfirmed. Editable provisional assumption - no confirmed local price	1	lot	$91.92	$91.92

Known subtotal (incomplete)	$1,930.17

PRELIMINARY BUDGET

Price pending

Assumptions

Original plan assumptions; current costs and overrides are in the line items. Gross walls, no openings deducted. Template coverage, productivity, expenses and margin are editable assumptions; catalog prices are public online observations, not local quotes.

Prepared by One Stop

Authorized signature image not configured.

Client acceptance

Client name: _____

Client signature: _____

Acceptance date: _____

Blank signature lines do not record acceptance.

Finalization records this saved revision. It is not customer acceptance or internal price approval.